

## Project Overview

Client: Mathews Developments  
Manufacturer: SIP Build  
Contractor: HA Construction  
Status: Complete



## Columbia Road, Poole – SIP Houses

Part of a development of ten houses, the main structure was supplied in 140mm thick SIP panels. The kitchen and bathrooms were also supplied using SIP, but these were first assembled into complete units by a sub contractor before being delivered to site complete.

The structure is primarily 140mm SIP panel manufactured from OSB and expanded foam, but with a compressive load capacity comparable with traditional masonry.

The project was delivered on time and on budget with minimal site works required.